Timothy Bowman, Supervisor Don La Porte, Clerk Bart Patterson, Treasurer



James Fraizer, Trustee John Honey, Trustee Matt Oddy, Trustee Tim Rush, Trustee

23480 Sumpter Rd., Belleville, MI 48111

www.sumptertwp.org

Addendum No. 001

Request for Proposal (RFP) Title: Membrane-Type Roof Section Replacement/Repair for the Police

Department

RFP Number: 252603

Date of Addendum: August 18, 2025

To all prospective respondents:

This Addendum is issued to modify, clarify, or amend the above-referenced Request for Proposal (RFP). This Addendum is hereby made part of the RFP documents.

Revisions and Clarifications:

Under "Contractor Requirements" section:

Clarification: The contractor shall be responsible for the following:

Clarification:

Contractor shall be responsible for the following:

- · Clean roof of all debris and prepare surface
- · Install 50 mil roofing system (tan color membrane) on the specified area to manufacturer's specifications
- · Install fan-fold separator sheet to manufacturer's specifications
- · All sections of material and accessories are to be welded into one complete sheet
- · Seal gutter edges and terminate
- · Install wall flashing on all walls
- · Install stack flashings on all stacks
- · Install 2-way breather vents
- · Install 2-piece metal fascia with 8-inch face (choice of standard Kynar 500 color)
- · Tear off all wet/saturated roofing materials and replace with new insulation thickness to match surrounding roof area
- · Install ¾ inch plywood over window area and cover with 1.5-inch insulation and membrane
- · Cover duct work of rooftop units with membrane