

# TOWN OF CHRISTIANA

## 2026 ROAD WORK

### CHIPSEALING

Sealed bids for roadwork will be accepted by the Town of Christiana until 9:00 a.m. Tuesday, May 7, 2026, at the Town Hall, 773 Koshkonong Road, Cambridge, WI 53523. Bids will be opened and read aloud at this time. Awarding bid(s) will take place at the Town Board meeting on May 11, 2026,

#### **2026 Town of Christiana Specifications for Chipsealing**

The Request for Bid (RFB) does not commit the Town of Christiana to award a contract, to pay any cost incurred in the preparation of a response to this request, or to procure or contract for services or equipment. The Town of Christiana reserves the right to accept or reject any or all bids received as a result of this request, or to procure or contract for services or equipment.

The Town of Christiana may accept a bid based on initial bids received, without discussion. Accordingly, each initial bid should be submitted on the most favorable terms from a price and technical standpoint.

1. Contact with Steve Brandt required prior to bidding (608)-423-3816
  2. A copy of this list must be filled out as is and included in bid to be considered.
  3. Contractor must supply town with proof of insurance.
  4. The completion date deadline is September 1st, 2026.
- 
- Contractor shall supply all labor, material and equipment to sign work zone.
  - Flaggers to be used on project for traffic control.
  - Clean existing surface with power broom immediately prior to applying the Emulsified Oil.
  - Apply CRS2 Emulsion Oil at a rate of 0.40 gals per Sq. Yd.
  - Cover with a 3/8" Fractured Peastone using a full width 24' chip spreader at 25lbs per Sq. Yd. Roll with two pneumatic rollers to embed stone.
  - Alternate stone: FA2 Black Granite or FA2 Dark Gray Granite.
  - CRS2 oil application on FA2 rock should be 0.32 Gal per SY.

Company Name-\_\_\_\_\_

Representative-\_\_\_\_\_

## **Quality Management and Warranty**

- The contractor shall guarantee the chipsealing for a period of not less than one (1) year from the date of chipsealing. Any defects as determined by the Town within this period shall be corrected by the successful bidder at their expense.

## **Construction Schedule**

- The work schedule will be one mutually agreed upon by the Town of Christiana and the successful bidder. All work shall be completed no later than September 1, 2026.

## **Terms and Conditions**

- A contract performance bond will be required from the successful bidder in the amount of 100% of the total bid price.
- The contract performance bond shall be executed and filed within 10 days after the contract award. This will be returned once the contract is executed.
- An umbrella certificate of insurance in the amount equal to total Town of Christiana project costs with a minimum amount of one million dollars (\$1,000,000.00). A contract will not be signed unless the certificates are provided.

## **Payment**

- Payment will be made only for supplied material accompanied by a ticket containing the following information:
  1. Ticket Number, Date, and Time
  2. Type of Material
  3. Net Weight

Load tickets must be from a certified scale.

**CHIPSEAL ROAD PROJECT:**

3/8” FRACTURED WASHED PEASTONE

ALTERNATE: FA2 BLACK OR DARK GRAY

CRS2 EMULSION TO BE USED

PROJECT:

E. CHURCH ROAD (Washington Rd. East to Hammen Rd.)

Approximately 11,800 ft. in length

CHIPSEAL PRICE USING 3/8” PEASTONE \$ \_\_\_\_\_

ALTERNATE:

CHIPSEAL PRICE USING FA2 BLACK \$ \_\_\_\_\_

CHIPSEAL PRICE USING FA2 GRAY \$ \_\_\_\_\_

**CONTRACTOR:**

AUTHORIZED SIGNATURE

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

**ACCEPTANCE OF BID:**

TOWN REPRESENTATIVE

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date