

Town of Christiana

2026 Hammen Rd. Roadwork Project

Sealed bids for roadwork will be accepted by the Town of Christiana until 9:00 a.m. Tuesday, May 5, 2026, at the Town Hall, 773 Koshkonong Road, Cambridge, WI 53523. Bids will be opened at this time. Awarding bid(s) will be at a later meeting to be announced.

2026 Town of Christiana Specifications for Road Bids

The Request for Bid (RFB) does not commit the Town of Christiana to award a contract, to pay any cost incurred in the preparation of a response to this request, or to procure or contract for services or equipment. The Town of Christiana reserves the right to accept or reject any or all bids received as a result of this request, or to procure or contract for services or equipment.

The Town of Christiana may accept a bid based on initial bids received, without discussion. Accordingly, each initial bid should be submitted on the most favorable terms from a price and technical standpoint.

Bidders may arrange a road inspection trip with the Town's highway foreman to better understand the project needs and to prepare a more accurate quote. A list of the Town's individual road projects and specifics are attached to this document.

Paving and/or Repaving

- Bidders MUST use the bid form below.
- The town will mark project limits prior to the bid posting.
- Incidental items not listed on the bid form but shall be included are:
 - Sweeping of existing roadway
- Work done by the township prior to contractor's mobilization:
 - Culvert work
 - Shouldering
- An asphalt pavement mixture of the type or types included in the contract shall be measured by the ton of mixed aggregates and bituminous material laid and compacted in place. The price shall be full compensation for producing, finishing, and placing all materials including, but not limited to asphalt, cement, and for all labor, tools, equipment, testing and incidentals necessary to complete the work.

Quality Management and Warranty

- The contractor shall guarantee the paving/repaving for a period of not less than one (1) year from the date of paving/repaving. Any defects as determined by the Town within this period shall be corrected by the successful bidder at their expense.

Traffic Control

- Traffic control shall be paid at the unit price on the bid form. Traffic control shall be provided by the contractor to maintain safety, minimize distress, and allow access to properties during construction and curing. The contractor will be responsible for all traffic control, including furnishing and maintaining all signs, flags, flag-persons, barricades, and lights where required, to protect the safety of the traveling public, all-in accordance with the Manual on Uniform Traffic Control Devices currently adopted by the Federal Highway Administration and the Wisconsin Department of Transportation supplement. All work shall be done under traffic unless otherwise directed by the Town.

Construction Schedule

- The work schedule will be one mutually agreed upon by the Town of Christiana and the successful bidder. All work shall be completed no later than August 31, 2026.

Terms and Conditions

- A contract performance bond will be required from the successful bidder in the amount of 100% of the total bid price.
- The contract performance bond shall be executed and filed within 10 days after the contract award. This will be returned once the contract is executed.
- An umbrella certificate of insurance in the amount equal to total Town of Christiana project costs with a minimum amount of one million dollars (\$1,000,000.00). A contract will not be signed unless the certificates are provided.

Payment

- Payment will be made only for supplied material accompanied by a ticket containing the following information:
 1. Ticket Number, Date, and Time
 2. Type of Material
 3. Net Weight

Load tickets must be from a certified scale.

Bid Form:

T/O CHRISTIANA - HAMMEN RD. 2" OVERLAY (FROM CHURCH RD. 7124' S.Y. TO TERMINI AS PAINTED)					
BID ITEM	DESCRIPTION	QUANTITY	UNIT	BID PRICE	BID TOTAL
1	TRAFFIC CONTROL	1	LS	\$	\$
2	MILLING BUTT JOINTS	1	LS	\$	\$
3	12.5MM HOT MIX ASPHALT - 2" PAVEMENT	851	TN	\$	\$
4	TACK COAT	444	GAL	\$	\$
				TOTAL	\$

Authorization of Bid (Contractor)

Signature: _____

Title: _____

Date: _____

Acceptance of Bid (Township)

Signature: _____

Title: _____

Date: _____