TOWN OF PROSPECT, CT
ADDENDUM FOR COACHLIGHT CIRCLE WATER MAIN

Please see the questions received and the answers for the Coachlight Circle water main project.

As a reminder, bids are due on or before November 16, 2026, at 1PM.

Question 1 Received: Are plans available?
Answer 1: Yes, the plans are attached here.

Question 2 Received: Is this for full time inspection and administration throughout?

Question 3 Received: What are the deliverables: daily reports, photos, tap cards, bacteria test and pressure test results, as-builts?

Answer 2&3: For questions 2 and 3 hear are expectations for inspection services -

- Provide a qualified Owner's Representative to be present on-site each day that construction activities are underway.
- Coordinate and facilitate communication between CWC, the Contractor, the Town of Prospect, and other project stakeholders, as necessary.
- Prepare daily construction observation reports, including photographic documentation of project progress.
- Maintain accurate field records and construction logs.
- Conduct field measurements and GPS data collection for all installed water main and water service infrastructure, including appurtenances and related facilities.
- Prepare and maintain tap cards for all newly installed water services, including applicable installation data and field-verified information.
- Prepare final Record Drawings documenting the completed installation and field-verified locations of all water mains, water services, appurtenances, and associated infrastructure upon completion of the project.