



VILLAGE OF MILLBROOK

35 MERRITT AVENUE PO BOX 349 MILLBROOK, NY 12545

TEL: 845-677-3939 FAX: 845-677-3972

VILLAGEOFMILLBROOKNY.COM

TIM COLLOPY
MAYOR

SARAH WITT
CLERK/TREASURER

NICOLE ZEKO
DEPUTY CLERK

Village of Millbrook Sewer Main Lining Project 2023

Install 8" Cured In Place Pipe for approximately 758 feet of sewer main. The work will be in three separate sections of sewer main. All sections of sewer main to be worked on are within easements. The section lengths are as follows:

Reservoir Dr MH79A-23 228 ft

This section is mostly clay tile pipe and includes about 15 feet of Cast Iron pipe, 2 capped laterals, and roots.

Elm Drive Alley MH45-44 295 ft

This section is mostly clay tile pipe and includes numerous roots, transition from clay to PVC, and broken pipe.

Maple Ave MH49A-49B 235 ft

This section is asbestos cement pipe and has infiltration.

Work shall include pipe cleaning and pre/post CCTV inspections. All CCTV inspection recordings are to be provided to the Village of Millbrook Water/Sewer Department upon completion. Maps of the sections to be lined are attached.

Ventilation of the sewer lines and surrounding area is required to ensure a safe environment for all residents in the work area. Exhaust shall be installed a minimum of 8 feet above any manhole rim.

Please contact Scott Osborn (scotto@vri-usa.com) with VRI Environmental Services with any questions regarding this work.

Regards,

Scott Osborn

Plant Manager

VRI Environmental Services